



महाराष्ट्र रेल इन्फ्रास्ट्रक्चर डेवलपमेंट कॉर्पोरेशन लि.

महाराष्ट्र शासन आणि रेल्वे मंत्रालय यांचा संयुक्त उपक्रम, २ रा मजला, हेक्ट हाऊस, नरीमन पॉईंट, मुंबई ४०००२१.

MAHARASHTRA RAIL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

A Joint Venture of Govt. of Maharashtra and Ministry of Railways

2nd Floor, Hoechst House, Nariman Point, Mumbai 400 021

Tel: +91 22 67477510 | Fax: +91 22 67477511 | Rly: 090 23700 | Email: info@maharail.com | Website: www.maharail.com

CIN: U74999MH2017SGC298367

CORRIGENDUM-1

Date: 09.10.2019

Name of Work: Construction of all civil works upto formation level including dismantling of existing Narrow Gauge line, Earthwork, blanketing, Major & minor bridges, Road Under Bridges (RUB)/ Limited Height Subway (LHS), retaining walls, drains, ground improvement works, cement concrete lining, cross drainage works, relocation of existing roads & utilities, Providing & fixing of Over Head Equipment mast etc. from Chainage 55.00 to Chainage 80.00 km in connection with Gauge Conversion Work between Umred to Mahuli Section in Nagpur Division of South East Central Railway.

Sub: Extension of Bid submission date, Revision in Specification of BOQ Item No. 28, addition of measurement condition and uploading of Project Sheet.

Ref: i) e- Tender No.: MRIDC/PROJ/e-TENDER/EW/2019/56

Following Corrections/Modifications/Addition shall please be carried out in subject tender:

SN	Reference Section	Reference Clause No.	Existing Description	Revised Description
1	Notice Inviting Tender (General Information Data Sheet)	2.29 (f)	Last date and Time of downloading/purchasing of Tender document 18.10.2019 14:58 hrs	Last date and Time of downloading/purchasing of Tender document 25.10.2019 14:58 hrs
		2.29 (g)	Last date and Time of uploading/submission of Tender document 18.10.2019; 15:00 hrs	Last date and Time of uploading/submission of Tender document 25.10.2019; 15:00 hrs
		2.29 (h)	Date and Time of Opening of Technical Bid 18.10.2019; 15:30 hrs	Date and Time of Opening of Technical Bid 25.10.2019; 15:30 hrs
2	Invitation for e-Tender		Interested Bidders can download the tender document from e-bidding portal of MRIDC from 18.09.2019 (18:00 hrs) to 18.10.2019 (14:58 hrs) after paying a non-refundable tender fee of Rs. 20,000/- through MRIDC's payment gateway available at e-bidding portal.	Interested Bidders can download the tender document from e-bidding portal of MRIDC from 18.09.2019 (18:00 hrs) to 25.10.2019 (14:58 hrs) after paying a non-refundable tender fee of Rs. 20,000/- through MRIDC's payment gateway available at e-bidding portal.
			Earnest Money Deposit (EMD) in prescribed format given in bid document shall be received at MRIDC's Corporate Office, Mumbai on or before 18.10.2019 (15:00 Hrs).	Earnest Money Deposit (EMD) in prescribed format given in bid document shall be received at MRIDC's Corporate Office, Mumbai on or before 25.10.2019 (15:00 Hrs).

3	<p>Section 7</p> <p>ADDITIONAL TECHNICAL SPECIFICATIONS</p> <p>(BOQ item NO. 28)</p>	7.20	<p>Excavation & Disposal of Bad formation/Black Cotton soil and Fill with approved material cohesive non swelling soil or material approved by MRIDC to original ground level and above. The rate is inclusive of Excavation of existing soil, spreading, grading, compacting of approved material with all leads & lifts etc. all in complete as per technical specification or as directed by Engineer in Charge. (BOQ Item No. 28)</p> <p>The work consists of Supply & Construction of cohesive non-swelling soil (CNS) layer, below the bottom layer of embankment fill in case of embankment and below subgrade/prepared subgrade level in case of cuttings, of suitably designed thickness and width, compacted to 98% of MDD. The CNS layer to be constructed by mechanical means with approved material to final designed cross section and levels as shown in the approved drawings and as per technical specification with all leads & lifts, dressing, watering, drying, compaction etc. as directed by the Client with all contractors own plant and machinery , materials & labours, tools including transportation, descend , crossing of nallahs/ streams and other obstructions, including all consumables, taxes, royalties, entry tax etc applicable, complete job to the full satisfaction. The rate shall include any extra quantity of fill to top up due to settlement as per RDSO/2007/GE:0014 (November 2009).</p>	<p>Excavation & Disposal of Bad formation/Black Cotton soil and Fill with approved material cohesive non swelling soil or material approved by MRIDC to original ground level and above. The rate is inclusive of Excavation of existing soil, spreading, grading, compacting of approved material with all leads & lifts etc. all in complete as per technical specification or as directed by Engineer in Charge. (BOQ Item No. 28)</p> <p>The work consists of Supply & Construction of cohesive non-swelling soil (CNS) layer, below the bottom layer of embankment fill in case of embankment and below subgrade/prepared subgrade level in case of cuttings, of suitably designed thickness and width, compacted to 98% of MDD. The CNS layer to be constructed by mechanical means with approved material to final designed cross section and levels as shown in the approved drawings and as per technical specification with all leads & lifts, dressing, watering, drying, compaction etc. as directed by the Client with all contractors own plant and machinery , materials & labours, tools including transportation, descend , crossing of nallahs/ streams and other obstructions, including all consumables, taxes, royalties, entry tax etc applicable, complete job to the full satisfaction. The rate shall include any extra quantity of fill to top up due to settlement as per RDSO/2007/GE:0014 (November 2009).</p> <p>Note:</p> <p>1. Minimum depth of excavation of Bad Formation/Black Cotton Soil shall be 1.0 meter or more as per specification and site condition, below Natural</p>
---	--	------	--	--

				<p><i>Ground Level and the same shall be filled with Cohesive Non-Swelling Layer or Material approved by MRIDC.</i></p> <p><i>2. The quantity mentioned in BOQ is calculated considering the above mentioned conditions.</i></p> <p><i>3. No extra payment shall be made with respect to change in quantity, if any of this item.</i></p>
4	New/Additional document uploaded	Project sheet indicating natural ground level, proposed formation level, station locations and alignment is being uploaded for entire stretch.		
5	Measurement Condition	<p>a. No field Measurement for earthwork/embankment (in cutting and filling including subgrade and blanket) shall be considered for payment and payment will be made as per quantity provided in BOQ.</p> <p>b. In case any change in formation level, during the execution of work, the payment will be made as per revised quantity calculated.</p> <p>c. For Structures i.e. Major Bridges, Minor Bridges, RUB/LHS, payment shall be made on the basis of quantity calculated from approved drawing/completion drawing.</p>		

Other terms & conditions of above said tender will remain unchanged. The corrigendum shall be part of the tender document.

**Sd/-
Managing Director
MRIDC**