



महाराष्ट्र रेल इन्फ्रास्ट्रक्चर डेवलपमेंट कॉर्पोरेशन लि.

महाराष्ट्र शासन आणि रेल्वे मंत्रालय यांचा संयुक्त उपक्रम, २ रा मजला, हेक्ट हाऊस, नरीमन पॉईंट, मुंबई ४०००२१.

MAHARASHTRA RAIL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

A Joint Venture of Govt. of Maharashtra and Ministry of Railways

2nd Floor, Hoechst House, Nariman Point, Mumbai 400 021

Tel: +91 22 67477510 | Fax: +91 22 67477511 | Rly: 090 23700 | Email: info@maharail.com | Website: www.maharail.com

CIN: U74999MH2017SGC298367

CORRIGENDUM-3

Date: 08.09.2020

Name of Work: Construction of all civil works upto formation level including dismantling of existing Narrow Gauge line, Earthwork, blanketing, Major & minor bridges, Road Under Bridges (RUB)/ Limited Height Subway (LHS), retaining walls, drains, ground improvement works, cement concrete lining, cross drainage works, relocation of existing roads & utilities, Providing & fixing of Over Head Equipment mast etc. from Chainage (-) 1.214 KM to Chainage 30.00 km and all Chord lines, shunting, Isolations/sand hump/cross overs etc. in all the station yards in connection with Gauge Conversion Work between Nagbhir to Bhiwapur Section in Nagpur Division of South East Central Railway.

Sub: Revision in provision adopted for various BOQ Items, Estimated Cost and value of EMD.

- Ref:** i) e- Tender No.: MRIDC/PROJ/e-TENDER/EW/2020/67
ii) Corrigendum No.: 1 Dated: 14.08.2020
iii) Corrigendum No.: 2 Dated: 31.08.2020

Following Corrections/Modifications/Addition shall please be carried out in subject tender:

A. The quantity considered in Bill of Quantity (Financial Bid) has been revised due to change in provisions. The change in provisions are as under: -

SN	BOQ Item No.	Short Description of Item	Earlier Provisions	Revised Provisions in this corrigendum
1.	26	Blanketing	Thickness of Blanketing considered 25 CM	Thickness of Blanketing considered 40 CM
2.	25	Subgrade	Thickness of Subgrade considered 50 CM	Thickness of Subgrade considered 85 CM
4.	24	Embankment/Earthwork Filling (Contractor's own earth)	Existing embankment of NG track considered to be taken in use.	Existing embankment of NG track considered not to be taken in use and shall be removed and refilled with good soil. Cutting & Filling quantity for the same has been considered in BOQ item No. 21, 23 & 24 respectively.
5.	23	Embankment/Earthwork Filling (Material Available at Site)		
6.	21	Earthwork in Cutting		
7.	28	CNS	CNS was considered for Ground improvement work.	CNS work not to be carried out. Ground Improvement, as and where necessary as per Geotechnical Report, to be carried out by replacing Black Cotton Soil (minimum 1 m or more) with good soil. Cutting & Filling quantity for the same has been considered in BOQ item No. 21, 23 & 24 respectively.

SN	BOQ Item No.	Short Description of Item	Earlier Provisions	Revised Provisions in this corrigendum
8.	20, 29.4, 30, 32.2, 33, 34.1, 34.2, 34.3, 35.1, 38, 39, 40, 41, 42, 43,44, 45, 46, 49.1, 49.2, 50, 51, 52, 53, 54, 55, 83	Structural Civil Work i.e. Major, Minor Bridges, RUB, LHS, Culverts etc	Pile Foundation was considered for Major Bridges.	Pile foundation for Major Bridges has been converted into Open Foundation. Length of Approach Roads etc has been changed.
9.	48	Credit for taking away dismantled / released materials	Material obtained by dismantling existing track of entire 30 KM shall be taken away by the contractor and respective credit shall be passed on to MRIDC.	Only 1033 MT of material obtained by dismantling existing track (as permitted by MRIDC) shall be taken away by the contractor and respective credit shall be passed on to MRIDC. Balance approximate 2362 MT materials shall be property of MRIDC and shall be properly stacked by the contractor at a nominated place by MRIDC.

Note:

- For SN 1 to 7 above table:** In case of changes in GE-14 due to further updation and existing formation to be use or not to be use, etc as the case may be, the changes shall be adopted in construction activities and contract value will be adjusted accordingly.
- For SN 8 & 9 of above table:** In case of changes in quantities, contract value shall be changed accordingly.
- Minimum Formation Width in embankment & in cutting (excluding side drains) should be 7.85 meter.

B. Revision in Earnest Money Deposit & Estimated Cost

SN	Reference Section	Reference Clause No.	Existing	Revised
1	Notice Inviting Tender: Value (Rs.)	2.1	151,57,70,058	157,65,08,371
2	Notice Inviting Tender : Earnest Money Deposit (Rs.)	2.1	77,28,750	80,32,550

C. Revised Bill of Quantity (Financial Bid) & revised drawings uploaded through Addendum-1.

All other terms & conditions of above said tender will remain unchanged. The corrigendum shall be part of the tender document.

**Sd/-
Managing Director
MRIDC**